

Resolution No. 212

*Resolution # 203 was  
rescinded by Res. # 216,  
hence this Resolution  
also*

WHEREAS, the Supply System, by letter dated September 1, 1982 requested an extension to the time window for construction in the Chehalis River to enable more expeditious completion of work near the river; and

WHEREAS, the Council has the authority to extend the time window for in-river construction work prescribed in the WNP-3 Site Certification Agreement Section III. G.4; and

WHEREAS, the Council by Resolution No. 203, adopted February 22, 1982 did direct that "construction activity in the Chehalis River must be confined to the period June 1 to September 15," (Ref: paragraph 7, Res 203); and

WHEREAS, the in-river work scope requested, removing piling and reclaiming a small bank area, will not have a significant effect on water quality or fish passage.

NOW, THEREFORE, BE IT RESOLVED, that the Energy Facility Site Evaluation Council does hereby authorize the requested extension of the in-river work time window for the requested activities through midnight September 30, 1982; and

IT IS FURTHER RESOLVED that the temporary modification to the water quality criteria for turbidity provided in Council Resolution No. 203 is also extended through midnight September 30, 1982 subject to the following condition:

During removal of bridge piles Dissolved Oxygen samples shall be taken at two hour intervals upstream at the approximate locations of the temperature sensors at 1' below water surface and 50' downstream from the pile bents being removed; in addition a turbidity sample shall be taken at the downstream locations. If Dissolved Oxygen falls below 8.0 ppm or turbidity exceeds 75 ppm at the downstream point of measurement pile removal shall be slowed or halted to maintain the respective limits of this paragraph. If a significant change of 2.0 ppm Dissolved Oxygen over a two hour period occurs the Council shall be notified. If no changes to water quality are evident from pile removal operations after the first day, sampling may be reduced to twice daily, and suspended after the third day if no further changes from ambient Dissolved Oxygen conditions are noted.

Provided further that during the period of this extension sufficient bridge clearance or opening shall be maintained to permit passage of recreational boating traffic at all times.

Dated this 13th day of September 1982.